

BOOM GATE INSTALLATION SERVICING AND MAINTENANCE SAFE WORK METHOD STATEMENT (SWMS)

Company Name:	OptiGroup Pty Ltd t/a Optilink Electrical & Communications	ABN:	19075861611	SWMS#:	—												
Company Address:	6/20-22 Parramatta St Cronulla 2230	SWMS Revision Date:	05/10/2026	SWMS Issue Date:													
Contact Person (Name):	Scott Wells	Email:	scott@optilink.com.au	Phone:	0418614154												
PROJECT PCBU APPROVAL																	
Full Name:	Scott Wells	Date:		Signature:													
Details of the person(s) responsible for ensuring implementation, monitoring & compliance of the SWMS as well as reviews and modifications of the SWMS:																	
Full Name(s):	Scott Wells	Title(s):	Director	Phone(s):	0418614154												
ALL PERSONNEL PARTICIPATING IN ANY ACTIVITY LISTED IN THIS SWMS MUST HAVE THE FOLLOWING COMMUNICATED:			NAME AND DATED SIGNATURES OF ALL RELEVANT PERSONNEL CONSULTED AND COMMUNICATED WITH IN THE DEVELOPMENT AND APPROVAL OF THIS SWMS:														
Brief workers before each job on site hazards and selected controls. Complete site-specific assessment and confirm scope, permits, competencies, PPE, emergency plan and the correct BFT manual. Supervisor monitors controls at each work stage.			<table border="1"> <thead> <tr> <th>NAME</th> <th>SIGNATURE</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>Scott Wells</td> <td></td> <td></td> </tr> <tr> <td>Kye Wells</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> </tr> </tbody> </table>			NAME	SIGNATURE	DATE	Scott Wells			Kye Wells					
NAME	SIGNATURE	DATE															
Scott Wells																	
Kye Wells																	
Stop if controls fail, conditions change or an incident occurs. Secure the area, review this SWMS and rebrief workers before restarting.																	
Any changes made to the SWMS after an incident or near miss must be approved by the PCBU and communicated to all relevant personnel.																	
The SWMS must be kept available for inspection until the work is completed. All versions should be kept when revised. If a notifiable incident occurs, the SWMS must be retained for at least 2 years.																	
CLIENT OR PRINCIPAL CONTRACTOR DETAILS																	

BOOM GATE INSTALLATION SERVICING AND MAINTENANCE SAFE WORK METHOD STATEMENT (SWMS)

Client Name:		Project Name:		SCOPE OF WORKS
Project Address:		SWMS Submission		BFT GIOTTO BT A ULTRA 36 XL ☐ Installation ☐ Service ☐ Repair Asset / serial: _____ Boom length: _____ Job / manual revision: _____ Isolation points: _____
Project Manager:		Contact Number:		
PM Signature:		Signature Date:		
HIGH-RISK CONSTRUCTION WORK BEING CARRIED OUT				
..	involves a risk of a person falling more than 2 meters	..	is carried out in or near a shaft or trench deeper than 1.5 m or a tunnel	
..	is carried out on a telecommunication tower	..	involves the use of explosives	
..	involves demolition of an element of a structure that is load bearing	..	is carried out on or near pressurised gas mains or piping	
..	involves, or is likely to involve, disturbing asbestos	..	is carried out on or near chemical, fuel or refrigerant lines	
..	involves structural alteration or repair that requires temporary support to prevent collapse	..	is carried out on or near energised electrical installations or services	
..	is carried out in or near a confined space	..	is carried out in an area that may have a contaminated or flammable atmosphere	
..	is carried out on, in or adjacent to a road, railway, shipping lane or other traffic corridor in use by traffic other than pedestrians	..	Other applicable high-risk construction work category: _____	
..	is carried out in an area of a workplace where there is any movement of powered mobile plant	..	is carried out in areas with artificial extremes of temperature	
..	Additional site hazards: _____	..	Select applicable categories after site assessment; do not preselect.	

JOB STEP	POTENTIAL HAZARDS	CONTROL MEASURES
1 Plan and secure site	Vehicle impact; public access; unexpected operation	Supervisor: close the lane and establish physical separation, signs and alternate pedestrian / vehicle access. Coordinate depot movements. Disable remote commands and confirm emergency access. Inspect weather and lighting; stop lifting in unsafe wind.
2 Isolate existing unit and remove	Shock; arc flash; boom movement; stored spring energy	Licensed electrician: identify all supplies including battery; isolate, lock and tag. Prove tester, test all relevant conductors, reprove tester. Secure boom and control spring energy by the exact BFT procedure before release, dismantling or removing the boom. A stop command is not isolation.
3 Locate services and form foundation	Buried services; silica; noise; excavation collapse	Supervisor: obtain service information and verify actual locations before digging, cutting or drilling. Apply dedicated excavation / cutting SWMS. Control dust at source with wet methods or suitable extraction; collect slurry and prevent discharge to drains. Confirm foundation design and curing before loading.
4 Lift position and anchor cabinet	Crushing; dropped load; unstable foundation	Competent installer: confirm load weight and lifting method, inspect lifting gear, maintain exclusion zone and keep hands clear. Use mechanical aids. Install correct anchors and foundation plate to the approved design and manufacturer requirements; verify stability and specified torque.
5 Fit boom spring and accessories	Spring release; sudden boom movement; pinch points	Competent BFT technician: match spring, mounting position and balance to actual boom length, lights, skirt and support accessories. Restrain / support the boom as specified. Follow the exact assembly and spring adjustment sequence. Do not remove the arm or spring attachments while energy is uncontrolled.
6 Install electrical and control wiring	Shock; damaged cables; incorrect safety wiring	Licensed electrician: work de-energised. Install supply, isolation, earthing, protection, glands and segregation as required. Wire photocells, loops and other devices to their manuals. Verify safety input configuration; never bypass safety devices to achieve normal operation.

JOB STEP	POTENTIAL HAZARDS	CONTROL MEASURES
7 Inspect and service isolated mechanism	Unexpected movement; cuts; stored energy	Technician: isolate all supplies and prevent remote actuation. Secure boom and follow manufacturer controls for spring energy. Inspect cabinet, anchors, boom, spring, linkage, release and drive. Replace defective parts with suitable manufacturer parts. Lubricate only specified points using specified products.
8 Test electrical installation	Shock; arc flash; unsafe supply	Licensed electrician: complete applicable installation verification and record results before energising. If testing requires exposed energised electrical parts, stop and implement the separate site-specific energised-work assessment, permitted justification, consultation, written PCBU authorisation, SWMS and observer requirements before proceeding.
9 Restore power for controlled motion tests	Struck by boom; crushing; remote start	Technician / supervisor: confirm tools removed, guards fitted, workers clear and safe configuration. Control re-energisation and commands. Keep exclusion zone across full boom travel and pinch points. Test from safe position with accessible emergency isolation. Isolate again before physical adjustments.
10 Set travel and operating sequence	Overtravel; impact; wrong speed or balance	Competent BFT technician: use settings suitable for the actual XL boom length and accessories. Check balance under manufacturer procedure; verify travel stops, slowdown, smooth movement and closing delay. Recheck safety functions after every change; record settings and error history.
11 Test each safety device	Vehicle / person impact; undetected failure	Technician: test photocells, presence loops, safety edges, stop controls and obstacle response as fitted. Verify actual response in relevant phases and fault monitoring where configured. Use suitable targets / instruments, never a person or vehicle for impact testing. Record method, readings and acceptance basis.

JOB STEP	POTENTIAL HAZARDS	CONTROL MEASURES
12 Handover or keep out of service	Unsafe operation; incomplete repairs	Supervisor: do not return unit with failed safety protection, insecure mounting or damaged spring. Isolate / tag, notify client and document repairs required. After successful repeated cycles and safety recheck, demonstrate release and controls, provide service report, settings, limitations and next service due. Remove barriers only after clearance.
Pre-start equipment PPE and emergency arrangements	Untrained workers; unsuitable equipment; inadequate rescue	Supervisor: verify induction, electrical licence and BFT mechanism competence; supervise apprentices. Check tools, testers, supports and lifting gear. Use safety footwear, high visibility clothing, eye / hearing protection and task gloves. Select respiratory / electrical PPE from task assessment. Record emergency isolation, first aider, kit, access and muster point. Call 000 in emergency; isolate before electrical rescue and use trained first aid / CPR.
Site-specific additions and monitoring	Unassessed hazards; changes; incomplete controls	Additional hazard: _____ Control / responsible person: _____ Emergency isolation / first aider: _____ Supervisor checks traffic separation, electrical isolation, spring energy and safety devices at each stage. Stop, review and rebrief if controls are inadequate or conditions change.
Work records and closeout	Missing records; unsafe return to use	Record inspection findings, electrical tests, safety response, force readings where applicable, settings, errors, photos, parts and outstanding defects. Client notified: _____ Next service: _____ Retain revised SWMS and relevant testing records. No signature is applied automatically.

LEGISLATIVE REFERENCES	
New South Wales Work Health and Safety Act 2011 Work Health and Safety Regulation 2025 Electrical risks and energised work; plant safety; high-risk construction work and SWMS duties. https://www.safework.nsw.gov.au/legal-obligations/legislation	SafeWork NSW guidance Construction Work Code of Practice Managing Electrical Risks in the Workplace Managing Risks of Plant in the Workplace Apply excavation, silica and traffic guidance where relevant.
Manufacturer instructions BFT GIOTTO BT A ULTRA 36 / XL and MERAK controller. Confirm exact Australian unit and accessory manuals. Manual / revision: _____ Spring and boom configuration: _____	Technical requirements Applicable AS/NZS 3000 installation and verification requirements, site electrical requirements, approved foundation design and BFT safety-device instructions. This SWMS requires site completion before use.
Energised testing This document does not authorise exposed energised electrical work. Complete separate site-specific assessment, permitted justification, consultation, PCBU authorisation and observer / rescue controls before that work.	Related task documents Excavation / trenching, concrete cutting / drilling, lifting, work at height and electrical testing as applicable. Routine minor maintenance is not automatically construction work; assess actual scope.
Document retention Keep SWMS and revisions available until high-risk construction work is complete. Retain for at least two years following a related notifiable incident. Apply separate energised-work record duties where applicable.	Site-specific review Complete site fields, select applicable high-risk categories, add local hazards and brief all workers. Supervisor verifies controls and obtains actual approval / signatures before work.
Service report Use Optilink Boom Gate Service and Inspection Report to record asset identification, results, defects, repairs, photos, return-to-service status and next service due.	
SIGNATORIES OF THE SAFE WORK METHOD STATEMENT (SWMS)	

BOOM GATE INSTALLATION SERVICING AND MAINTENANCE SAFE WORK METHOD STATEMENT (SWMS)

The signed and dated personnel listed below have cooperated in the consultation and development of this Safe Work Method Statement which has been approved by the Person/s Conducting a Business or Undertaking (PCBU). In signing this Safe Work Method Statement each individual acknowledges and confirms that they have read this SWMS in full, having raised any questions for items on this Safe Work Method Statement that require clarification, and confirms that they are competent, skilled and knowledgeable for the task assigned to them. Every person acknowledges that they have received the relevant training and qualifications where required, before carrying out any work contained in this Safe Work Method Statement. By signing this Safe Work Method Statement each individual agrees to work safely, to follow any safe work instructions which are provided, and agrees to use all Personal Protective Equipment where appropriate.

Full Name:	Scott Wells	Date:		Signature:		Position:	Director/ Electrician
Full Name:	Kye Wells	Date:		Signature:		Position:	Apprentice Electrician
Full Name:		Date:		Signature:		Position:	
Full Name:		Date:		Signature:		Position:	
SWMS REVIEW NUMBER	1	2	3	4			
NAME & INITIALS (SIGN-OFF)	Scott Wells						
DATE							