

ELECTRICAL EQUIPMENT & CABLING JSA RISK ASSESSMENT

Coding Legend									
Consequence:									
Minor	Green	Indicates low impact, minor consequences that are easily manageable.							
Moderate	Yellow	Indicates a moderate level of impact that may require additional controls.							
Major	Orange	Indicates serious consequences that could potentially lead to significant issues.							
Severe	Red	Indicates very serious consequences that could result in critical or catastrophic outcomes.							
Likelihood:									
Unlikely	Green	Indicates that the occurrence is not expected, but possible.							
Possible	Yellow	Indicates a fair chance of the event occurring, should be prepared for.							
Likely	Orange	Indicates a high chance of the event occurring, immediate attention needed.							
Risk Rating:									
Low	Green	Represents a low level of risk; monitoring is required, but immediate action may not be necessary.							
Medium	Yellow	Represents a moderate level of risk; it requires specific monitoring and planning to manage.							
High	Red	Represents a high level of risk; immediate action and intervention are necessary to mitigate risks.							
Task/Activity	Potential Hazard	Persons at Risk	Consequence	Likelihood	Initial Risk Rating	Mitigation Measures	Residual Consequence	Residual Likelihood	Residual Risk Rating
Site risk assessment and planning	Live/unidentified circuits; poor planning	Workers, others	Severe	Possible	High	Complete a site-specific risk assessment. Identify sources/circuits, review drawings and permits, consult the PCBU, confirm competent licensed workers and record controls.	Moderate	Unlikely	Low
Set up temporary power	Shock; overload; inadequate earthing	Workers, others	Severe	Possible	High	Licensed electrician only. Provide compliant RCDs, earthing and labelled boards; verify load, inspect/test before energising and restrict access.	Major	Unlikely	Medium
Inspect tools and equipment	Damaged cords, plugs, insulation or fittings	Workers	Major	Possible	High	Perform pre-use checks. Remove, tag and quarantine damaged items; use lock-out/tag-out where applicable and report defects.	Moderate	Unlikely	Low
Test and tag equipment	Expired tags; inaccurate tests; faulty items	Workers, others	Major	Possible	High	Competent person to use calibrated, in-date test equipment. Record results, affix tags, quarantine failures and notify the supervisor.	Moderate	Unlikely	Low
Use leads and powerboards	Trips; overheating; exposed connections	Workers, public	Major	Possible	High	Use tested industrial equipment with RCD protection. No piggybacking. Protect or elevate leads; keep plugs dry/secure and inspect during use.	Moderate	Unlikely	Low
Run cables and conduit	Crushing; sharp edges; trips; hidden services	Workers, public	Major	Possible	High	Locate services before cutting/drilling. Isolate as required. Use supports/covers, protect edges, avoid traffic routes, sign and inspect cable runs.	Moderate	Unlikely	Low
Connect equipment to power	Shock; arc flash; surge; loose connection	Workers	Severe	Possible	High	Isolate and prove de-energised where practicable. Lock/tag/test-before-touch. Check ratings and connections; use suitable weatherproof fittings.	Major	Unlikely	Medium
Operate handheld tools	Shock; malfunction; cuts; noise; vibration	Workers	Severe	Possible	High	Use tested/tagged tools to manufacturer instructions. Check guards, maintain footing, wear required PPE and disconnect before adjustment.	Moderate	Unlikely	Low
Monitor electrical usage	Overload; overheating; electrical fire	Workers, others	Severe	Possible	High	Monitor loads, temperature and condition. Keep combustibles clear; stop, isolate, tag and report equipment showing heat, damage or odour.	Major	Unlikely	Medium
Respond to faults	Current; arc flash; burns; fire; re-energisation	Workers, others	Severe	Possible	High	Stop and isolate; lock/tag and test for dead. Prevent access. Licensed electrician only to repair. Evacuate and use emergency plan for fire/arc.	Major	Unlikely	Medium
Disconnect and pack up	Residual energy; damage; manual handling	Workers	Major	Possible	High	Follow shutdown sequence: isolate and prove dead. Inspect, store safely and use mechanical aids/team lifts. Complete pack-down check.	Moderate	Unlikely	Low
Maintain signs/exclusion zones	Unauthorised entry; poor visibility; trips	Workers, public	Major	Possible	High	Install and maintain compliant signs, barriers and clear access. Replace damaged signs and reposition controls as the work area changes.	Moderate	Unlikely	Low
Communicate hazards	Unaware workers; changed conditions; wrong method	Workers, others	Major	Possible	High	Cover hazards in induction, pre-starts and toolbox talks. Confirm understanding; communicate changes and stop if controls are ineffective.	Moderate	Unlikely	Low
Audit compliance	Non-compliance; missed checks; poor records	Workers, others	Major	Possible	High	Audit tags, RCD tests, supplies, registers and controls. Record, assign and verify corrective actions; escalate unresolved high risks.	Moderate	Unlikely	Low

OEC-JSA001

ELECTRICAL EQUIPMENT & CABLING JSA RISK ASSESSMENT



Final inspection and sign-off	Defects; exposed parts; unsafe handover	Workers, client, public	Severe	Possible	High	Licensed electrician to inspect and test. Reinstate covers, remove hazards, complete records, communicate residual risks and obtain sign-off.	Moderate	Unlikely	Low
SIGNATORIES OF THE JSA RISK ASSESSMENT									
The signed and dated personnel listed below have cooperated in the consultation and development of this JSA Risk Assessment which has been approved by the Person/s Conducting a Business or Undertaking (PCBU). In signing this JSA Risk Assessment each individual acknowledges and confirms that they have read this JSA Risk Assessment in full, having raised any questions for items on this JSA Risk Assessment that require clarification, and confirms that they are competent, skilled and knowledgeable for the task assigned to them. Every person acknowledges that they have received the relevant training and qualifications where required, before carrying out any work contained in this JSA Risk Assessment. By signing this JSA Risk Assessment each individual agrees to work safely, to follow any safe work instructions which are provided, and agrees to use all Personal Protective Equipment where appropriate.									
Full Name:		Date:		Signature:		Position:			
Full Name:		Date:		Signature:		Position:			
Full Name:		Date:		Signature:		Position:			
Full Name:		Date:		Signature:		Position:			