

COMMUNICATIONS & DATA CABLING JSA RISK ASSESSMENT

Coding Legend									
Consequence:									
Minor	Green	Indicates low impact, minor consequences that are easily manageable.							
Moderate	Yellow	Indicates a moderate level of impact that may require additional controls.							
Major	Orange	Indicates serious consequences that could potentially lead to significant issues.							
Severe	Red	Indicates very serious consequences that could result in critical or catastrophic outcomes.							
Likelihood:									
Unlikely	Green	Indicates that the occurrence is not expected, but possible.							
Possible	Yellow	Indicates a fair chance of the event occurring, should be prepared for.							
Likely	Orange	Indicates a high chance of the event occurring, immediate attention needed.							
Risk Rating:									
Low	Green	Represents a low level of risk; monitoring is required, but immediate action may not be necessary.							
Medium	Yellow	Represents a moderate level of risk; it requires specific monitoring and planning to manage.							
High	Red	Represents a high level of risk; immediate action and intervention are necessary to mitigate risks.							
Task/Activity	Potential Hazard	Persons at Risk	Consequence	Likelihood	Initial Risk Rating	Mitigation Measures	Residual Consequence	Residual Likelihood	Residual Risk Rating
Site induction and planning	Unknown hazards; poor coordination; inadequate planning	Workers, others	Major	Possible	High	Complete induction and pre-start. Review drawings, cable routes, existing services, permits and access. Nominate the team leader, allocate responsibilities and agree communications with the site supervisor.	Moderate	Unlikely	Low
Deliver and handle cable drums	Strain; crush injury; slips and trips	Workers	Major	Possible	High	Plan the route, inspect drums and use mechanical aids or team lifts. Wear gloves and safety footwear, secure drums on level ground and use rated cable stands where required.	Moderate	Unlikely	Low
Store materials onsite	Blocked access; trips; collapse; weather damage	Workers, public	Major	Possible	High	Use the designated storage area. Keep exits and walkways clear, protect cable from moisture/UV, stack and secure materials, restrict access and inspect storage daily.	Moderate	Unlikely	Low
Access ceiling spaces	Falls; heat stress; dust; hidden electrical hazards	Workers	Severe	Possible	High	Complete a ceiling-space risk check and isolate electrical hazards where required. Use an inspected platform/ladder, maintain three points of contact, barricade below, wear dust/eye PPE and monitor heat, hydration and access.	Major	Unlikely	Medium
Install cable trays or supports	Falls; dropped objects; sharp edges	Workers, public	Severe	Possible	High	Use inspected ladder/EWP and fall protection where required. Establish an exclusion zone, secure tools, stage materials to reduce overhead handling and wear cut-resistant gloves. Verify supports and fixings before loading.	Major	Unlikely	Medium
Pull and run cables through ceilings	Strain; cable burns/snags; trips; falls	Workers	Major	Possible	High	Plan the route and use rollers/pulling equipment. Protect sharp edges, coordinate feeding and pulling teams, wear gloves, control trailing cable and stop if snagged or obstructed.	Moderate	Unlikely	Low
Run cables through risers or shafts	Falls; dropped objects; restricted access	Workers, others	Severe	Possible	High	Restrict riser access and establish an exclusion zone below. Use required fall protection and rated rope/winch systems, secure tools/materials and maintain reliable team communications.	Major	Unlikely	Medium
Run cables in underground pits	Confined space; hazardous atmosphere; water; existing services	Workers	Severe	Possible	High	Inspect for water and atmosphere hazards. Treat as confined space where applicable: permit, trained team, atmospheric testing, ventilation, standby person and retrieval equipment. Locate utilities and secure pit lids/barriers.	Major	Unlikely	Medium
Use hand and power tools	Shock; cuts; noise; flying particles	Workers	Severe	Possible	High	Use tested/tagged and inspected tools to manufacturer instructions. Fit guards, disconnect before adjustment, wear eye/hearing/hand PPE and store tools safely after use.	Moderate	Unlikely	Low
Terminate and dress cables	Fine cuts; eye strain; repetitive strain	Workers	Moderate	Possible	Medium	Use correct stripping and termination tools, eye protection and gloves. Work at a suitable height, vary posture and take micro-breaks. Remove offcuts and inspect terminations.	Minor	Unlikely	Low
Install patch panels or outlets	Pinch injury; falling equipment; poor fixings	Workers, others	Major	Possible	High	Support panels until secured, use assistance for heavy items and select fixings for the substrate. Wear gloves, check alignment and tighten securely before releasing the load.	Moderate	Unlikely	Low

Test and commission cabling	Shock from test equipment; incorrect results; faulty equipment	Workers, client	Major	Possible	High	Use approved, calibrated testers; inspect and prove equipment before use. Do not test live unless authorised and specifically controlled. Wear appropriate PPE, record results and quarantine/report faulty equipment.	Moderate	Unlikely	Low
Work near other services	Strike electrical, gas, water or communications services	Workers, others	Severe	Possible	High	Review drawings and positively locate services using suitable detection. Establish clearances/exclusion zones and use a spotter near hazards. Stop and report any unidentified service before proceeding.	Major	Unlikely	Medium
Maintain housekeeping	Trips; fire load; blocked access	Workers, public	Major	Possible	High	Keep exits and walkways clear, maintain lighting, control trailing cable, promptly collect scrap/offcuts in suitable bins and complete end-of-shift clean-up.	Moderate	Unlikely	Low
Decommission and remove old cabling	Asbestos/dust; cuts; manual handling; hidden services	Workers, others	Severe	Possible	High	Identify services and possible ACM before disturbance. Isolate where required; stop and follow the asbestos plan if suspected. Wear respiratory/hand PPE, use safe handling, dispose lawfully and update the decommissioning register.	Major	Unlikely	Medium

SIGNATORIES OF THE JSA RISK ASSESSMENT

The signed and dated personnel listed below have cooperated in the consultation and development of this JSA Risk Assessment which has been approved by the Person/s Conducting a Business or Undertaking (PCBU). In signing this JSA Risk Assessment each individual acknowledges and confirms that they have read this JSA Risk Assessment in full, having raised any questions for items on this JSA Risk Assessment that require clarification, and confirms that they are competent, skilled and knowledgeable for the task assigned to them. Every person acknowledges that they have received the relevant training and qualifications where required, before carrying out any work contained in this JSA Risk Assessment. By signing this JSA Risk Assessment each individual agrees to work safely, to follow any safe work instructions which are provided, and agrees to use all Personal Protective Equipment where appropriate.

Full Name:		Date:		Signature:		Position:	
Full Name:		Date:		Signature:		Position:	
Full Name:		Date:		Signature:		Position:	
Full Name:		Date:		Signature:		Position:	